

Open Spaces Supporting Documents

3rd September 2025

Agenda item 6.1

Please see image below of a court divider net. Awaiting price.



Agenda item 7.1

Installation of an earth bund between the Pavilion and tennis courts with wooden posts placed on top.

Contractor 1	Contractor 2
Allow to remove for re-use current dragons' teeth. Remove both bins, black bin is to self-site and site by large red waste bin in car parks space. Small red bin is to be relocated on small concrete slab to match existing to the rear of the new bund. Creation of bank using subsoil to form the profile and dress in topsoil. Allow to deliver and collect excavator to site. Supply subsoil (inert). Bank to be profiled to achieve constant line and contour where possible. Contour of gradient to be sharp to prevent vehicles from being able to drive over/on the bank. Top of the bank is to have a flat top where possible. Supply 20 tons of Topsoil (ex Winchester screened recycled). Allow to topsoil the bank entirely	To build bund along carpark – supply all materials & Labour £3000.00 +VAT

by 75mm in thickness. (we can do this thicker should you require but we assume the bank is of a soil make up). Variation would apply. Allow to seed with grass seed and press roll. Press in the saved dragons teeth to the top of the bund, no allowance to concrete as instructed. Future maintenance and watering by others not included in this quotation.
£3290 +VAT



Agenda item 7.3

Suspended fencing to go around the Oak tree on the recreation ground to prevent ill use.



- Anti-climb mesh
- Reinforced corners
- Fully galvanised weather resistance
- Rapid deployment, installation and repositioning
- Non-permanent fixing, ideal for temporary fencing and security
- Round top
- Easy to customise with logos and banners



<ul style="list-style-type: none"> • Relatively lightweight for easy transportation, stacking and storage • Range of foot-types and couplings available • Available for delivery across the UK, for both hire or purchase <p>2m x 3.45m Price requested</p>	
<p>2025mm [H], 3450mm [W]</p> <p>3 fence panels £77.40+VAT</p> <p>Anti-tamper couplers £1.12 each Anti-tamper coupler spanner £26.30 Plastic feet £7.70 each 50kg ballast block £36.73 each</p>	
<ul style="list-style-type: none"> • 3.5m (W) x 2m (H) • Manufactured in Britain • Galvanised steel finish • x1 Fence Panel, x1 Fence Foot and x2 Fence Clips per set <p>price for 3 sets - £89.97 +VAT Delivery £59.99</p>	

Agenda item 8.1

Area update – tree felled on cricket field behind container.

Email from contractor:

The team were very impressed by the gnarled character of the birch stem and left it standing about 2.5m tall as a habitat pole, as it would make an ideal habitat for borers and other insects. I did say we would fell it to ground level on the quote, so if you would like it on the floor we can return and fell the stem, but I can see why they left it standing like this as now it does not pose any hazard and it is ideal habitat for wildlife.





Revetments at Swelling Hill Pond.



Green surface on pond.



Badger Orchard strimmed by the Lengthsman.

Agenda item 9.2

<https://commemorativeconvoys.org.uk>